BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Construction of Public Toilets at Parks in ward no. 04 Yelahanka New Town

Work Order No: EE (Project)/Ynk Zone/WO/ 10/2020-21 Dt:- 07/05/2020

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. K S Chowdareddy	
				In figures	In words
1	552.73	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications in hard soil.	Cum	499.00	Rupees Four Hundred Ninety Nine Only
2	214.00	Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications.	m	596.56	Rupees Five Hundred Ninety Six And Paise Fifty Six Only
3	38.52	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications,	Cum	2292.78	Rupees Two Thousand Two Hundred Ninety Two And Paise Seventy Eight Only
4	7.00	Constructing brick masonry circular type manhole 1.22 m internal dia at bottom, 1.68 m deep and 0.56m dia at top, with table moulded and non modular bricks of class designation 50 in cement mortar 1:4, inside cement plaster 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and down size granite metal and making necessary channel in cement concrete M 15 with 20mm and down size granite metal, finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming to IS :12592, total weight length of cover and frame to be not less than 182 kg, fixed in cement concrete M 15 20mm and down size broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately)	Nos	32630.93	Rupees Thirty Two Thousand Six Hundred Thirty And Paise Ninety Three Only
5	514.21	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	134.67	Rupees One Hundred Thirty Four And Paise Sixty Seven Only
6	67.41	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	2101.34	Rupees Two Thousand One Hundred One And Paise Thirty Four Only
7	23.75	Providing 12mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. KSRB15-3.2 : – do – cement mortar 1:4.	Sqm	214.20	Rupees Two Hundred Fourteen And Paise Twenty Only
8		GST @ 12%			

K.S. Chowdareddy

Contractor

Executive Engineer
Project Division
Yelahanka Zone